

### SUBMITTAL DATA - OUTDOOR UNIT VPB240L4M-3G

### VPB120L4M-3G + VPB120L4M-3G

### **VRF Heat Pump**

Heat Pump Outdoor Unit	For: Poforonco	Approval	Poviow	Construction
System Designation:	Date:			
Schedule No.:	Location:			
Location:	Architect:			
Job:	Engineer:			

### **FEATURES**

- Split coil heat exchanger
- · Dual hinged electrical boxes for ease of
- · High-efficiency vapor injection inverter compressor
- · Intelligent Duty Cycle operation
- · Night Silent operation
- · Hinged service doors
- · Built-in service console

- · Built-in base pan heater
- · Heating Operation down to -22F
- · Low Ambient Cooling down to -10F w/ kit

### WARRANTY

- · Compressor 10-year limited warranty
- All other components 10-year limited warranty \*See warranty for details

SPECIFICATIONS		
PERFORMANCE		
Cooling Capacity <sup>1</sup> (Btu/h)	Nominal	240,000
(=·····)	Rated <sup>2</sup>	230,000
EER	Ducted	11.3
	Non-Ducted	11.4
IEER	Ducted	22.1
	Non-Ducted	23.5
Heating Capacity¹ (Btu/h)	Nominal	270,000
	Rated <sup>2</sup>	258,000
COP47	Ducted	3.70
	Non-Ducted	3.75
COP17	Ducted	2.50
	Non-Ducted	2.38

ELECTRICAL DATA	
Power Supply (Volts/Phase/Hertz)	460/3/60
Minimum Circuit Ampacity (A)	43+43
Maximum Overcurrent Protection (A)	45+45
Compressor RLA (A)	(2) 17+17
Number of Compressors	(2) 2
Outdoor Fan Power Input (W)	(2) 1200/1200
Outdoor Fan FLA (A)	(2) 2.2/2.4
GENERAL DATA	
Connection Ratio	50% to 130%
Maximum Number of Indoor Units	44

Catacor rain Ex (7.)	(2) 2.2/2.4
GENERAL DATA	
Connection Ratio	50% to 130%
Maximum Number of Indoor Units	44
Refrigerant Type	R-410A
Factory Refrigerant Charge (each unit)	23.8 lbs.

### **NOTES**

Cooling and Heating capacity data is rated at the following

Cooling: 80°FDB / 67°FWB Indoor, 95°FDB Outdoor

Heating: 70°FDB Indoor, 47°FDB / 43°FWB Outdoor.

- Complies with AHRI 1230-2014 testing standards
- Operating Voltage Range 410V to 525V
- To achieve cooling lower than 5°F a Low ambient hood must be installed. This is purchased as an accessory.
- A local 115V power outlet is available as an accessory to provide local power for maintenance.



DIMENSIONS	(Each Module)							
Unit	Height	72						
Dimensions (in)	Width	68-1/2						
	Depth	32-5/8						
Main System Piping (in)								
Liquid Pipe Connection	n	3/4						
Gas Pipe Connection		1-1/4						
Balancing Pipework between Modules (in)								
L.P. Gas Balance Pipe Connection	Э	1-1/4						
H.P. Gas Balance Pip Connection	е	3/4						
Oil Balance Pipe Con	nection	5/16						
Unit Net Weight (lb)		1076						








# SUBMITTAL DATA - OUTDOOR UNIT VPB240L4M-3G VPB120L4M-3G + VPB120L4M-3G VRF Heat Pump

DIMENSIONAL DRAWINGS - INCHES (MM)												
<b>CORNER WEIGHTS</b>									CENTE	R OF GR	AVITY	
Model No.	Α	Α	В	В	С	С	DD		EE		FF	
	lbs.	kg	lbs.	kg	lbs.	kg	lbs.	kg	in.	mm	in.	mm
VPB120L4	173	80	266	122	332	153	323	148	37-1/2	953	12	305



NOTE – Due to Lennox' ongoing commitment to quality, Specifications, Ratings and Dimensions subject to change without notice and without incurring liability. Improper installation, adjustment, alteration, service or maintenance can cause property damage or personal injury.

Installation and service must be performed by a qualified installer and servicing agency.

495872 (202206) ©2022 Lennox Industries Inc.

**BASE PAN VIEW** 




## SUBMITTAL DATA - OUTDOOR UNIT VPB240L4M-3G VPB120L4M-3G + VPB120L4M-3G

# VRF Heat Pump


### **MULTI-MODULE INFORMATION**

#### **Multi-Module Dimensions**



**NOTE** - All the outdoor units manifolded together should be installed at the same elevation.

#### **Multi-Module Power**



See page 1 for electrical data.

Total system MCA is calcuated by adding the MCA value of each module together to get the total system MCA.

Total system MOP is calcuated by adding the MOP value of each module together to get the total system MCA.